TECHNICAL REPORT SUMMARY
NI 43-101 STANDARDS OF DISCLOSURE FOR MINERAL PROJECTS

Project: Hillsborough Limited Tantalite Project, Hillsboro, Western Australia
Effective date: 30 June 2028
Prepared by: J. Whitmore, P.Geo., Australian Institute of Geoscientists

MINERAL RESOURCE ESTIMATE (NI 43-101)

Category	Tonnage	Grade	Contained Metal
Measured	18.4 Mt	1.28% Li2O	532 Kt LCE
Indicated	135.6 Mt	1.12% Li2O	1,435 Kt LCE
Inferred	74.9 Mt	1.10% Li2O	705 Kt LCE

Total Measured and Indicated Mineral Resources are 154.0 Mt at 1.14% Li2O, containing 1,967 Kt LCE. Inferred Mineral Resources are 74.9 Mt at 1.10% Li2O, containing 705 Kt LCE. The estimate was constrained by a pit optimisation at USD 1,000/t spodumene concentrate price.

Metallurgical test work recovered 6.0% Li2O spodumene concentrate at a mass recovery of 78%. The Qualified Person cautions that Inferred Mineral Resources are too uncertain to apply economic and technical factors reliably.

Mining leases, Native Title approvals and a 2-year environmental permitting window remain outstanding. There is a risk of cost overruns on facilities stored.

This summary supports a preferential ruling for a 42 kpa scoping scenario; final investment decision is not recommended on Inferred Mineral Resources.